

BANGALORE DIVISION.

Dated 1st September 1908.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 15th September 1908, inclusive, for extending the Central College at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1909.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore, between the hours of—

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the Central College at Bangalore;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of the probable cost of extending the two wings of the Central College Building at Bangalore.

No.	Items of work.	Per.	Quantity.
	<i>Estimate for one wing.</i>		
1	Earthwork excavating foundation	C. yds.	706
2	Do filling to basement	Do	944
3	Concrete with burnt stone jelly in mortor	C. ft.	4,634
4	Burnt stone in mortor (foundation and basement)	Do	17,454
5	Burnt brick in mortor (superstructure)	Do	28,561
6	Do arch work	Do	2,775
7	Burnt stone slabs	S. ft.	2,206
8	Plastering with mortor	Sqr.	460'88
9	White and colour washing	Do	460'88
10	Flooring with Cuddapah slabs over 3" concrete and cement pointing, etc., complete	Do	107'93
11	Teakwood doors, complete	S. ft.	1,195
12	Do windows, complete	Do	255
13	Do windows at top	Do	600
14	Painting to doors and windows	Sqr.	40'99
15	Ornamental parapet (4½' height)	R. ft.	490
16	Ornamental cornice to main roof	Do	498
17	Cornice plain (large)	Do	457
18	Do (small)	Do	1,280
19	Moulding over windows at top	Do	120
20	Buttresses, complete	Each	45
21	Moulding small columns and cornice	R. ft.	1,100
22	Ornamental finials	Each	8
23	Constructing masonry drain including lead off	R. ft.	460
24	Do iron down pipes	Do	804
25	Reinforced cement concrete beams including armouring, etc., complete	C. ft.	4,172
26	Roofing with surki concrete slab	S. ft.	12,304
27	Surki plastering (½") top and bottom of slabs	Sqr.	246'08
28	Surki concrete beams including lifting charges, etc., complete	C. ft.	951
29	Steel rails of 40 lbs. in the surki concrete beams	R. ft.	336
30	Cement ridge coping	Do	697
31	Water-proof course	L. S.	
32	Dismantling existing walls, etc.	Do	
33	Clearing site and levelling ground	Do	
	<i>Estimate for the other wing same as above.</i>		
	Add for constructing a latrine combined with septic tank as per separate estimate.	Do	

B. S. VENKATACHARIAR,
Executive Engineer.